

SINCE 1972

July 21, 2025

City of San Luis Obispo 25 Prado Rd. San Luis Obispo, CA 93401

PROPOSAL



Sourcewell Contract Number: 022014-EVS

RE: Proposal for One (1) Envirosight Rovver X System and Chassis Retrofit

<u>Description</u>	Price:
CCTV Van Retrofit	\$13,765.00
Equipment will be installed in San Luis Obispo's existing CCTV Van. All components	
will remain and be reused with new equipment.	
New flooring in rear Equipment Area of the van. All existing components removed, new marine grade plywood and new flooring installed, existing components reinstalled.	
New 21.5" HD monitors installed, one rear facing in the Equipment Area, and one mounted in the Office Area.	
New Light Package: (2) Traffic Advisors one front facing one rear facing, Corner Strobes (4), and Roof Mounted Beacons front and rear.	
New Tow Hitch Assembly	
MEPS Alternator with Pulley	\$3,839.67
Rovver X Pro Package:	\$110,292.80
RCX90 HD Zoom Camera; high-resolution CCD color zoom camera with 10x optical and 12x digital zoom, auto shutter, auto/manual focus, built-in LED lighting, +/-135-degree tilt, endless 360-degree rotation, pressure sensor, and twin laser diodes for measuring feature.	
RVX 130 Crawler; Steerable crawler with two-high performance motors and 6-wheel drive. Includes pressure indicator, inclination and tilt sensors, location transmitter, integral Back-eye camera, and clutch.	
VC500 Control Panel; 10" Touch screen, joystick crawler/camera control, digital recording/jpeg, built in inspection software PACP based.	
RAX300 Automatic Motorized Cable Reel; with meter/footage counter, splash-proof rating, 1000' orange transmission cable; power supply for 115/230V; remote control (for equipment set up); patch cable with e-stop (connecting DCX5000 to RAX300).	
Pressurization Kit; Regulator, air valve, and two (2) CO2 Canisters, for replacing air	



SINCE 1972

\$22,205.21
\$22,205.21
\$2,600.74
\$1,589.34
\$2,369.00
\$3,079.70
\$20,972.88
\$202,919.55
\$17,755.46
\$1,000.00
\$220,675.01